

## Project Case Study

### Owner

**Odwalla**  
1900 Davis Drive  
Dinuba, CA 93618

### Project

**Plant Sump Pit Lining**  
1900 Davis Drive  
Dinuba, CA 93618



## Project Summary

**Substrate**  
Pre-Cast Concrete

**Surface Preparation**  
SSPC-SP 13

**System**  
Envirolite® 290 Organic Acid  
Lining

**Project Completion Date**  
Spring 2004

## Project Description

All of the drains and water at this natural juice manufacturing plant flow to one pit. Obviously after years of installing standard epoxies and coal tar epoxies, Odwalla engineers had enough of the constant corrosion and maintenance.

They turned to Polytech Industrial, Inc. to solve the problem.

Polytech abrasive blasted the pit to remove all existing coatings and create a deep profile for the 40.0 mil thick Envirolite® Organic Acid Lining that would be applied. The lining was applied and the pit returned to service.

Sounds easy right? Consider that the pit was only out of service for 18 hours total!

Another Polytech Industrial, Inc. solution!